BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

NAME OF WORK: Construction of cement concrete road and improvements to to drain In BB Nagara and Maruthinagara in ward no.8 Kodigehalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	260.00	Removing B.S slab of drain and stacking	sqm	63.72	Rupees Sixty Three and Seventy Two Paise Only
2	286.00	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	83.16	Rupees Eighty Three and Sixteen Paise Only
3	42.90	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement 220kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @o.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5236.92	Rupees Five Thousand Two Hundred Thirty Six and Ninety Two Paise Only
4	111.15	Providing laying plain/ reinforced cement concrete for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc.complete as per approved drawing and design MORTH specification No.1500, 1700, 2200. M20 Grade using Concrete mixer	cum	6931.44	Rupees Six Thousand Nine Hundred Thirty One and Forty Four Paise Only
5	7.22	Providing T.M.Tsteel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members whereever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	onne	59327.91	Rupees Fifty Nine Thousand Three Hundred Twenty Seven and Ninety One Paise Only
6	286.00	Providing and fixing RCC 1:2:4 Precast slab for covrering using 20mm and Downsize granite jelly as per design including necessary centering, forming, Curing and finishing with CM 1:3 etc complete 250mm thick	sqm	5111.00	Rupees Five Thousand One Hundred Eleven Only
7	361.00	Lead for disposal of debris shall be payable at carrage rates by mechanical means including loading and unloading From 13.30 Kms	cum	123.20	Rupees One Hundred Twenty Three and Twenty Paise Only

No of corrections - Nil

30/12

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

30/12

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಾರು ಬೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುವಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ತಿದ್ದುವಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ 06.01.17